



March 14th, 2025

CHELAN COUNTY NATURAL RESOURCE DEPARTMENT
PESHASTIN CREEK RM 4.3 SIDE CHANNEL PROJECT

ADDENDUM NO. 1

To the Contractors, Subcontractors, Planholders and Suppliers:

The following items contain additions, deletions, or modifications to the Plans and/or Specifications. This Addendum forms as a part of the Contract Documents. All updated contract Documents can be found at <https://www.co.chelan.wa.us/natural-resources/pages/current-opportunities>.

Bidders must acknowledge receipt of this Addendum on the Bid Proposal Declaration within the Bid Package.

BID PACKAGE

1. BIDDING INSTRUCTIONS

- 1.1. The date of bid opening in the first sentence of “Point A: Bid Opening” is corrected to “Monday March 24th, 2025.”

SPECIAL PROVISIONS

2. Division 8: MICELLANEOUS CONSTRUCTION

The following revisions have been made to Section 8-19 to clarify the measurement and payment of the “Individual Bank Buried Rootwads” Bid Item.

- 2.1. Section 8-19.5 Measurement:** The second paragraph is revised to read:

The Bid Item for “Individual Bank Buried Rootwads” will be measured per each Log with Rootwad installed. This Bid Item includes each individual log placed in the Bank Buried Structures and the Inlet Structures. The rock component of the Inlet Structures is measured and paid under Section 2-05.


- 2.2. Section 8-19.6 Payment:** The second and third paragraphs are revised to read:

The Bid Item for “Individual Bank Buried Rootwads” will be paid per each Log with Rootwad installed. This Bid Item includes each individual log placed in the Bank Buried Structures and the Inlet Structures. The rock component of the Inlet Structures is measured and paid under Section 2-05.

The unit price for each structure type, including “Individual Bank Buried Rootwads”, includes the following: furnishing, hauling, and temporary staging of woody material; all labor, materials, preparation and installation of slash and slash bundles; hauling, and placement of any additional necessary materials as shown on the project plans; site preparation, excavation and backfill associated with placement of logs; hauling logs and materials to and from onsite stockpile; placement of logs; final grading for a smooth transition; installation of all mechanical

connections as shown on the Plans; performing Vertical Pile Log pullout resistance testing, and placement and compaction of backfill, and other Work that may be needed.

END OF ADDENDUM NO. 1

X 

Hannah Pygott, Sr. Natural Resource Specialist
Chelan County Natural Resources Department